


Basement Floor



$$U_{eq\ F-G} = \frac{4.951}{54.0 \cdot 2.667} = 0.0344\ \text{Btu}/(\text{h} \cdot \text{ft}^2 \cdot \text{F}) \qquad = R-29.1$$

Boundary Condition					Material	$\lambda[\text{Btu}/(\text{h} \cdot \text{ft} \cdot \text{F})]$
	$q[\text{Btu}/(\text{h} \cdot \text{ft}^2)]$	$\theta[^\circ\text{F}]$	$h[\text{Btu}/(\text{h} \cdot \text{ft}^2 \cdot \text{F})]$	ε		
Exterior, ventilated		14.000	1.355		Air layer, unventilated, upwards, thickness: 40 mm	0.144
Interior, heat flux, downwards		68.000	1.036		GWB (Typ) [R-0.85/in]	0.098
Symmetry/Model section	0.000				Plywood (Typ) [R-1.2/in]	0.069
					Rockwool Comfortbatt 7.25in [R-4.14/in]	0.020
					Wood, Coniferous (Softwood) [R-1.03/in]	0.081
					Wood, Deciduous (Hardwood) [R-0.91/in]	0.092