


Below-grade Wall



$$U_{eq \text{ C-D}} = \frac{4.185}{33.408 \cdot 2.667} = 0.0470 \text{ Btu}/(\text{h}\cdot\text{ft}^2\cdot\text{F}) = R-21.3$$

Boundary Condition	$q[\text{Btu}/(\text{h}\cdot\text{ft}^2)]$	$\theta[^\circ\text{F}]$	$h[\text{Btu}/(\text{h}\cdot\text{ft}^2\cdot\text{F})]$	ε
Exterior, NYC 90d Avg		34.592	4.403	
Interior, normal, horizontal		68.000	1.355	
Symmetry/Model section	0.000			

Material	$\lambda[\text{Btu}/(\text{h}\cdot\text{ft}\cdot\text{F})]$
Air layer, unventilated, horizontal, thickness: 40 mm	0.128
Brick (Common) [R-0.2/in]	0.416
GWB (Typ) [R-0.85/in] (1)	0.098
Mortar - Portland Cement-Lime (PHI)	0.520
Roxul SmartRock [R-4.2/in]	0.020
Steel (Rolled, Ground) [R-0.0029/in]	28.889
Stucco [R-0.2/in]	0.417