


Extension Wall



$$U_{eq \text{ C-D}} = \frac{6.576}{54.0 \cdot 2.667} = 0.0457 \text{ Btu}/(\text{h}\cdot\text{ft}^2\cdot\text{F}) = R-21.9$$

Boundary Condition					Material	$\lambda[\text{Btu}/(\text{h}\cdot\text{ft}\cdot\text{F})]$
	$q[\text{Btu}/(\text{h}\cdot\text{ft}^2)]$	$\theta[^\circ\text{F}]$	$h[\text{Btu}/(\text{h}\cdot\text{ft}^2\cdot\text{F})]$	ϵ		
Exterior, normal	14.000	4.403	4.403		Air layer, unventilated, horizontal, thickness: 40 mm	0.128
Interior, normal, horizontal	68.000	1.355	1.355		Brick (Common) [R-0.2/in]	0.416
Symmetry/Model section	0.000				CMU (8in Empty Cores) [R-0.14/in]	0.600
					GWB (Typ) [R-0.85/in] (1)	0.098
					Mortar - Portland Cement-Lime (PHI)	0.520
					Roxul SmartRock [R-4.2/in]	0.020
					Steel (Rolled, Ground) [R-0.0029/in]	28.889
					Slightly ventilated air cavity *	
					* Simplified approach	